

**TABLE A - BID FORM**

Form For General Bid: City of Valdosta Water Treatment Plant No. 2 and Production Wells					
Part	Description	UOM	Unit Rate	Planned Quantity	Total
<b>1</b>	<b>Allowances</b>				
a	Permitting	LS		1	
b	Site signage	LS	\$20,000	1	\$ 20,000.00
c	Surge Mitigation Devices	LS		1	\$ 200,000.00
d	Construction Contingency (10% of total bid)	LS		1	
<b>2</b>	<b>Production Wells Nos. 1 and 2</b>				
a	Well piping, pumps, fittings, valves, and appurtenances; concrete slabs for wellhead assembly and pipe supports; sitework including containment curb/crushed stone/seedling and sodding; electrical and instrumentation features as shown on Drawings and necessary communications with process equipment.	LS		1	\$ -
<b>3</b>	<b>Water Treatment Plant</b>				
a	Clearing, grubbing, disposal and site access preparation (includes erosion and sedimentation control along fencelines), Grading and seeding for erosional control, Site access road, WTP loop road, site security fence, security gate and card-reader, Excavation for stormwater pond, stormwater site grading, transfer of on-site fill, Sidewalks, walkways, curbs, and parking spaces on site, degasification complex, chemical injection vault, chemical storage area and CO2 tank, operations building, sanitary grinder pump station.	LS		1	\$ -
<b>4</b>	<b>Ground Storage Tank</b>				
a	1.0-million gallon prestressed concrete ground storage tank with all necessary appurtenances and piping (hatch, ladders, manways), as shown on Drawings, electrical items and instrumentation connections for ground storage tank.	LS		1	\$ -
<b>5</b>	<b>Yard Piping Outside Fence</b>				
a	Raw water, finished water, and sanitary sewer piping along the site access road from Well No. 2 and to the tie-in locations.	LS		1	\$ -
<b>6</b>	<b>Mobilization/Demobilization</b>				
a	Mobilization/Demobilization fee (no more than 5% of total bid)	LS		1	\$ -
	<b>TOTAL BASE BID</b>				
<b>7</b>	<b>Alternative Bid Item No. 1: Removal of Canopy Covering Chemical Storage Area</b>				
a	Removal of canopy covering the chemical storage area.	LS		1	\$ -
<b>8</b>	<b>Alternative Bid Item No. 2: Substitution of Asphalt Millings for Limerock Roadway</b>				
a	Line the site access road with the City's stockpile of asphalt millings. Ratio shall be 25% millings and 75% limerock.	LS		1	\$ -
<b>9</b>	<b>Alternative Bid Item No. 3: Addition of Baffle Curtain to GST</b>				
a	Install a baffle curtain inside the ground storage tank.	LS		1	\$ -
<b>10</b>	<b>Unit Price Item No. 1: Remove Unsuitable Soils and Import Fill</b>				
a	Provide a unit price in \$/CY for removing unsuitable soils and importing fill. This unit price will be used if the soils on-site are determined to be unsuitable soils.	CY		--	
	LS - Lump Sum; CY = Cubic Yard				
	<b>TOTAL BASE BID + BID ALTERNATES</b>				